

ADDENDUM NO. TWO (2)

CONSTRUCT EXECUTIVE HANGAR & ASSOCIATED SITE WORK

**DINWIDDIE COUNTY AIRPORT
PETERSBURG, VA**

**AIP Project No. 3-51-0039-PENDING
Delta Project No. VA 08100**

JULY 7, 2010

From: Delta Airport Consultants, Inc.
P. O. Box 80036 (mailing address)
1750 E. International Blvd, Suite #3 (shipping only)
Raleigh, North Carolina 27623

To: All Bidders of Record



This Addendum is hereby made a part of the contract documents and specifications of the above referenced project. All other requirements of the original specification shall remain in effect in their respective order. Acknowledge receipt of this addendum by inserting its number and date in the proposal form.

SPECIFICATIONS

Table of Contents

1. **REVISE** Part VIII-Roadway of the Table of Contents to include specification R-606VA, Pages R-606-1 thru R-606-2.

Proposal

2. **DELETE** item number 43 of Alternate 1 on page P-8 of the proposal.

Part VIII - Roadway

3. **ADD** Specification R-606VA, Attachment Two (2) of Addendum Two (2) to the end of the Roadway section.

ATTACHMENTS:

1. Questions and Answers
2. Specification R-606VA

END OF ADDENDUM NO. ONE (1)

QUESTIONS AND ANSWERS

- 1. QUESTION:** Please clarify what type of materials can be placed in the on-site waste area.

ANSWER: Topsoil and any excess suitable soils may be stockpiled in the on-site waste area shown on the plans. All unsuitable soils must be hauled and disposed of offsite.
- 2. QUESTION:** Items 42 and 43 on Alternate One (1) are the same specification. Is this correct?

ANSWER: No. Per Addendum No. Two (2) Item 43 has been removed from Alternate One (1) of the proposal. Specification R-606VA was added to the Roadway section of the specs.
- 3. QUESTION:** How will stone subbase under the building be paid for?

ANSWER: The stone subbase under the Executive Hangar will be considered incidental to the Executive Hangar foundation which is item number 23 of Alternate One (1) and Alternate Two (2).

ITEM R-606 SOIL RETENTION COVERINGS

R-606VA

DESCRIPTION

606-1.1 This work shall consist of furnishing and placing protective coverings for soil retention, including seed, fertilizer, lime, topsoil, and water, in accordance with these specifications and in reasonably close conformity to the dimensions, line, and grades shown on the plans or as established by the Engineer.

MATERIALS

606-2.1 Materials shall conform to VDOT, Road and Bridge Specifications, 2007, Section 244.02(K), EC-2.

CONSTRUCTION METHODS

606-3.1 The equipment and construction methods for the installation of the soil retention coverings shall conform to VDOT, Road and Bridge Specifications, 2007, Section 606.

METHOD OF MEASUREMENT

606-4.1 Protective coverings and soil stabilization mats will be measured in square yards of area covered, complete-in-place, in accordance with nominal plan dimensions, and will be paid for at the contract unit price per square yard. Overlaps, overwidths, and cut slots will not be measured for separate payment.

BASIS OF PAYMENT

606-5.1 The accepted quantities of soil retention coverings will be paid for at the contract unit price per square yard, which price shall be full compensation for furnishing, installing, and stapling soil retention coverings; smoothing and shaping ditch channels and waterways; preparing seed beds; and furnishing and applying topsoil, lime, seed, fertilizer, and water, and for all labor, tools, equipment, and incidentals necessary to complete the item.

R-606-1

ITEM R-606 SOIL RETENTION COVERINGS

Payment will be made under:

Item R-606-5.1 Soil Stabilization mat

-- per square yard

END OF ITEM R-606