

SUMMMARY OF QUANTITIES

As-Bid

Alternate I

Expand Terminal Parking Lot

Georgetown - Scott County Regional Airport
Georgetown, Kentucky

KDA Project No. KY 10-87

Delta Project No. KY 10060

Date: June 11, 2010

| Item No. | Section No. | Description | Unit | Bid Quantity |
|----------|-------------|--|------|--------------|
| 1 | 110 | MOBILIZATION | LS | 1 |
| 2 | 110 | DEMOBILIZATION | LS | 1 |
| 3 | 112 | MAINTAIN AND CONTROL TRAFFIC | LS | 1 |
| 4 | 201 | STAKING | LS | 1 |
| 5 | 203 | PAVEMENT REMOVAL | SY | 75 |
| 6 | 204 | ROADWAY EXCAVATION | LS | 1 |
| 7 | 212 | TOPSOIL FURNISHED AND PLACED | CY | 50 |
| 8 | 212 | SEEDING AND PROTECTION | SY | 700 |
| 9 | 212 | SODDING | SY | 110 |
| 10 | 213 | STONE CONSTRUCTION ENTRANCE | EA | 1 |
| 11 | 213 | SILT CHECK | EA | 2 |
| 12 | 213 | CULVERT INLET PROTECTION | EA | 1 |
| 13 | 213 | SILT TRAP - TYPE A | EA | 2 |
| 14 | 213 | TEMPORARY SILT FENCE | LF | 500 |
| 15 | 214 | FABRIC - GEOTEXTILE, TYPE III | SY | 1,650 |
| 16 | 302 | DENSE GRADED AGGREGATE BASE | TN | 900 |
| 17 | 403 | CL3 ASPH SURF 0.38D PG64-22 | TN | 400 |
| 18 | 403 | CL3 ASPH BASE 0.75D PG64-22 | TN | 310 |
| 19 | 408 | ASPHALT PAVEMENT MILLING AND TEXTURING | TN | 220 |
| 20 | 505 | CONCRETE SIDEWALK, 4" | SY | 110 |
| 21 | 506 | HEADER CURB | LF | 1,150 |
| 22 | 701 | CULVERT PIPE, 15" RCP CLASS V | LF | 56 |
| 23 | 701 | REMOVE PIPE | LF | 30 |
| 24 | 710 | SLOPED BOX OUTLET, TYPE I, 15" | EA | 2 |
| 25 | 713 | PAVEMENT STRIPE - PERMANENT PAINT, 4" | LF | 2,000 |
| 26 | 713 | PAVEMENT STRIPE - PERMANENT PAINT, 12" | LF | 130 |
| 27 | 713 | HANDICAP MARKING | EA | 2 |
| 28 | SP-24 | RELOCATE LIGHT POLE | LS | 1 |
| 29 | SP-25 | 2" PVC SPLIT DUCT | LF | 250 |
| 30 | SP-26 | 2" PVC CONDUIT | LF | 40 |
| 31 | SP-27 | UNDERCUT EXCAVATION | CY | 270 |