

SUMMARY OF QUANTITIES**As-Bid****Alternate II****Expand Terminal Parking Lot**

Georgetown - Scott County Regional Airport
 Georgetown, Kentucky

KDA Project No. KY 10-87

Delta Project No. KY 10060

Date: June 11, 2010

Item No.	Section No.	Description	Unit	Bid Quantity
1	110	MOBILIZATION	LS	1
2	110	DEMOBILIZATION	LS	1
3	112	MAINTAIN AND CONTROL TRAFFIC	LS	1
4	201	STAKING	LS	1
5	203	PAVEMENT REMOVAL	SY	75
6	204	ROADWAY EXCAVATION	LS	1
7	212	TOPSOIL FURNISHED AND PLACED	CY	50
8	212	SEEDING AND PROTECTION	SY	700
9	212	SODDING	SY	110
10	213	STONE CONSTRUCTION ENTRANCE	EA	1
11	213	SILT CHECK	EA	2
12	213	CULVERT INLET PROTECTION	EA	1
13	213	SILT TRAP - TYPE A	EA	2
14	213	TEMPORARY SILT FENCE	LF	500
15	214	FABRIC - GEOTEXTILE, TYPE III	SY	1,350
16	302	DENSE GRADED AGGREGATE BASE	TN	750
17	403	CL3 ASPH SURF 0.38D PG64-22	TN	370
18	403	CL3 ASPH BASE 0.75D PG64-22	TN	250
19	408	ASPHALT PAVEMENT MILLING AND TEXTURING	TN	220
20	505	CONCRETE SIDEWALK, 4"	SY	110
21	506	HEADER CURB	LF	1,000
22	701	CULVERT PIPE, 15" RCP CLASS V	LF	56
23	701	REMOVE PIPE	LF	30
24	710	SLOPED BOX OUTLET, TYPE I, 15"	EA	2
25	713	PAVEMENT STRIPE - PERMANENT PAINT, 4"	LF	1,800
26	713	PAVEMENT STRIPE - PERMANENT PAINT, 12"	LF	130
27	713	HANDICAP MARKING	EA	2
28	SP-24	RELOCATE LIGHT POLE	LS	1
29	SP-25	2" PVC SPLIT DUCT	LF	250
30	SP-26	2" PVC CONDUIT	LF	40
31	SP-27	UNDERCUT EXCAVATION	CY	270